KAUFMAN COUNTY OUTER LOOP

Texas Department of Transportation

KAUFMAN COUNTY OUTER LOOP

PUBLIC MEETING

DATE:	STATE DISTRICT:	COUNTY:	CONTROL NO.:	SEC NO.:	JOB NO.:
09/09/2024	DAL	KAUFMAN	0918	11	100

FUNCTIONAL CLASSIFICATION			RAMP	ARRAY
Maintained	Outer Loop	Rural Freeway	15 MPH	4.0%
	US 80	Interrupted	15 MPH	4.0%
	US 80	Urban/Principal Arterial	15 MPH	4.0%
Frontage Road	Outer Loop	Urban/Major Collector	15 MPH	4.0%
	US 80	Urban/Principal Arterial	15 MPH	4.0%
	US 80	Urban/Principal Arterial	40 MPH	4.0%
Direct Connect		Major Collector	40 MPH	4.0%
			30 MPH	4.0%
Ramps		Major Collector	30 MPH	4.0%
Cross Street	SH205	Urban/Principal Arterial	45 MPH	4.0%
	Colquitt Rd	Urban/Major Collector	45 MPH	4.0%
	FM 741	Rural/Local Street	45 MPH	4.0%
	Samuels Rd	Rural/Local Street	45 MPH	4.0%
	Sage Hill Pkwy	Rural/Local Street	45 MPH	4.0%
	Future Arterial	Rural/Local Street	45 MPH	4.0%
	CR 239	Rural/Local Street	45 MPH	4.0%

KAUFMAN
TEXAS COUNTY MAP
N.T.S.

INDEX OF SHEETS		
ROLL 1-6	PLAN: BEGIN STA. 10 TO END STA. 1000+00.00	KCOL
ROLL 7-8	PLAN: STA. 1012+00.00 TO END STA.2000+00.00	IH20
ROLL 9-10	PLAN: STA. 2100+00.00 TO 2170+00.00	IH-20

DISTRICT ENGINEER: CESION CLEMENS, P.E.

PROJECT LOCATION MAP
KAUFMAN COUNTY



PROJECT LENGTH 8.07 Miles

STATE PLANE NAD 1983 North Central Texas FIPS 4202 Feet
SURFACE TO GRID FACTOR: 1.00012487

SCALE 1"=100' H

FEDERAL AID PROJECT NO.		PRELIMINARY SUBJECT TO REVISIONS SCHEMATIC PREPARED BY OR UNDER THE DIRECT SUPERVISION OF:		
FED. AID DIV. NO.	HIGHWAY NO.	REVISED BYRD NAME	DIRECT P.E. NUMBER	PRELIMINARY
TXD	IH20			NOT FOR CONSTRUCTION, BIDDING OR PERMIT PURPOSES
		DATE		STATE OF TEXAS, DAVID L. HAYNES, JR. P.E. NO. 75-R, DATE: 11/ 1/ 2024

ROLL 7 OF 10

HDR
Firm Registration No. F-754
17111 Preston Road, Suite 300
Dallas, Texas 75248-1232
972.980.4400

℄ IH-20
℄ FRES
℄ FRES
℄ IH20
℄ IH20
℄ IH20